

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes ☐
no ☐

Property Name: Taylor's Venture Inventory Number: CE-148
Address: 168 Winch Road City: Perryville Zip Code: 21903-1619
County: Cecil USGS Topographic Map: Harve De Grace
Owner: George F. & George W. Porter Is the property being evaluated a district? ☐ yes
Tax Parcel Number: 30 Tax Map Number: 68 Tax Account ID Number: _____
Project: Roadway Structures of CSX Railroad Agency: Cecil County Department of Public Works
Site visit by MHT Staff: ☒ no ☐ yes Name: _____ Date: _____
Is the property located within a historic district? ☐ yes ☒ no

If the property is within a district

District Inventory Number: _____

NR-listed district ☐ yes Eligible district ☐ yes District Name: _____

Preparer's Recommendation: Contributing resource ☐ yes ☐ no Non-contributing but eligible in another context ☐

If the property is not within a district (or the property is a district)

Preparer's Recommendation: Eligible ☒ yes ☐ no

Criteria: ☒ A ☐ B ☒ C ☐ D Considerations: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☒ None

Documentation on the property/district is presented in:

Description of Property and Eligibility Determination: *(Use continuation sheet if necessary and attach map and photo)*

Taylor's Venture is located in the Perryville vicinity of Cecil County north of U.S. 40 on the east side of Winch Road. The majority of the property is west of the Principio Creek and south of the CSX Railroad. The property consists of a dwelling, a barn, and nine agricultural outbuildings. All buildings except for a modern cement-block office/shop contributed to the historic integrity of the farmstead. The farmstead sets on a hill and is surrounded by rolling agricultural fields, wooded areas, and a small pond. The main dwelling and barn date to the late-eighteenth and early-nineteenth centuries, both with additions from subsequent historical periods. The majority of the outbuildings date to the first half of the twentieth century, with the exception of the non-contributing office/shop. The dwelling at Taylor's Venture is a three-part house consisting of a brick, a stone, and a frame portion. Variation in the height of each section and linear connection to each other gives the house a unique telescopic look. The landscape surround the farmstead's cluster of buildings still reflects the historic appearance of agricultural farm fields and wooded areas.

Taylor's Venture is eligible for the National Register of Historic Places under Criterion A for agriculture and Criterion C for architecture. The property is not associated with individuals significant in history (Criterion B) and has not been evaluated for its ability to yield information important in prehistory or history (Criterion D). The property has been in agricultural use since the eighteenth century and its buildings are reflective of centuries of Cecil County's rich, rural architectural history.

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended ☒ Eligibility not recommended ☐

Criteria: ☒ A ☐ B ☒ C ☐ D Considerations: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None

Comments: _____

Tom Tom Quindt
Reviewer, Office of Preservation Services

Blum
Reviewer, NR Program

4/21/04
Date

5/5/04
Date

200400849

MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORMContinuation Sheet No. 1

The property maintains its original *location* on the west bank of Principio Creek. The *design* of the largest portion of the dwelling exhibits a rural, vernacular interpretation of Federal architecture, particularly noticeable in the decorative detail of the original front door surround, windows, and dormers. Quality *workmanship* is evident in the brick and stone construction of the dwelling, as well as the stonework on the property's main barn. In addition, buildings on the property retain a high percentage of original *materials*, such as slate roofs and original wooden sash windows. As there is little modern development in the surrounding area and the majority of the property remains in productive agricultural use, the property's *setting* retains a high level of historic integrity. Taylor's Venture continues to impart a *feeling* of eighteenth, nineteenth, and early twentieth century agriculture. The property has no significant *association* with persons or events important in history.

Prepared by: Melissa Hess, KCI TechnologiesDate Prepared: February 9, 2004

CAPSULE SUMMARY
Taylor's Venture (CE-148)
168 Winch Road
Perryville vicinity
c. 1800
Private

Taylor's Venture is located in the Perryville vicinity of Cecil County north of U.S. 40 on the east side of Winch Road. The majority of the property is west of the Principio Creek and south of the CSX Railroad. The farmstead sets on a hill and is surrounded by rolling agricultural fields, wooded areas, and a small pond. The property consists of a dwelling, a barn, and nine agricultural outbuildings. The dwelling and barn date to the late-eighteenth and early-nineteenth centuries, both with additions from subsequent historical periods. The majority of the outbuildings date to the first half of the twentieth century, with the exception of a non-contributing office/shop. The dwelling at Taylor's Venture is a three-part house consisting of a brick, a stone, and a frame portion. Variation in the height of each section and linear connection to each other gives the house a unique telescopic look. The landscape surround the farmstead's cluster of buildings still reflects its historic appearance of agricultural farm fields and wooded areas.

Taylor's Venture is eligible for the National Register of Historic Places under Criterion A for agriculture and Criterion C for architecture. The property has been in agricultural use since the eighteenth century and its buildings are reflective of centuries of Cecil County's rich, rural architectural history.

The seat of the Taylor family for generations, Taylor's Venture dates to the early eighteenth century. A 1720s map notes the area as "Thomas Taylor's Land." The first European ownership of this land was as part of a large patent granted to Irishman George Talbot in 1680 with the provision that he bring six hundred and forty persons of British or Irish descent to settle the area at his own expense. The name Taylor's Venture most likely originated with John Taylor, who deeded the property to his sons in the late 1790s. Members of the Taylor family continued to own the land until the mid-nineteenth century. Subsequent owners divided the land over the years. By the early twentieth century, the property was once again combined to its original acreage from three separate deeds. In the 1940s, owners restored the dwelling to its original colonial appearance.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. CE-148

1. Name of Property (indicate preferred name)

historic Taylor's Venture
other The End of All Strife: Strife's End

2. Location

street and number 168 Winch Road not for publication
city, town Perryville x vicinity
county Cecil

3. Owner of Property (give names and mailing addresses of all owners)

name George F. and George W. Porter
street and number 168 Winch Road telephone
city, town Perryville state MD zip code 21903-1619

4. Location of Legal Description

courthouse, registry of deeds, etc. Cecil County Land Records liber 1352 folio 569
city, town Elkton tax map 30 tax parcel 68 tax ID number 07 009976

5. Primary Location of Additional Data

 Contributing Resource in National Register District
 Contributing Resource in Local Historic District
 Determined Eligible for the National Register/Maryland Register
 Determined Ineligible for the National Register/Maryland Register
 Recorded by HABS/HAER
 Historic Structure Report or Research Report at MHT
 Other:

6. Classification

Category	Ownership	Current Function	Resource Count
<u> </u> district	<u> </u> public	<u> X </u> agriculture	Contributing
<u> X </u> building(s)	<u> X </u> private	<u> </u> commerce/trade	<u> 9 </u>
<u> </u> structure	<u> </u> both	<u> </u> defense	<u> </u>
<u> </u> site		<u> </u> domestic	<u> </u>
<u> </u> object		<u> </u> education	<u> </u>
		<u> </u> funerary	<u> 9 </u>
		<u> </u> government	<u> </u>
		<u> </u> health care	<u> 1 </u>
		<u> </u> industry	<u> </u>
		<u> </u> landscape	Noncontributing
		<u> </u> recreation/culture	<u> 1 </u> buildings
		<u> </u> religion	<u> </u> sites
		<u> </u> social	<u> </u> structures
		<u> </u> transportation	<u> </u> objects
		<u> </u> work in progress	<u> </u> Total
		<u> </u> unknown	
		<u> </u> vacant/not in use	
		<u> </u> other:	

**Number of Contributing Resources
previously listed in the Inventory**

7. Description

Inventory No. CE-148

Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins
<input type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

Taylor's Venture is located in the Perryville vicinity of Cecil County north of U.S. 40 on the east side of Winch Road. The majority of the property is west of the Principio Creek and south of the CSX Railroad. The property consists of a dwelling, a barn, and nine agricultural outbuildings. All buildings except for a modern cement-block office/shop contributed to the historic integrity of the farmstead. The farmstead sets on a hill and is surrounded by rolling agricultural fields, wooded areas, and a small pond. From Winch Road, a gravel lane lined with Cedar trees approaches the farmstead's cluster of historic buildings. The main dwelling and barn date to the late-eighteenth and early-nineteenth centuries, both with additions from subsequent historical periods. The majority of the outbuildings date to the first half of the twentieth century, with the exception of the non-contributing office/shop (Photographs 1-2).

The dwelling at Taylor's Venture is a three-part house consisting of a brick, a stone, and a frame portion. Variation in the height of each section and linear connection to each other gives the house a unique telescopic look, particularly when viewed from the front façade, or south elevation (Photograph 3).

The largest portion of the dwelling is a two-and-one-half story, gabled roof, brick structure, three bays long and two bays deep, with two exterior end brick chimneys. This portion sits on a clearly visible stone foundation, as the basement is raised. The brickwork on all four elevations is common bond, though the brickwork on the front façade is of slightly higher quality workmanship than the other three sides. The windows of the front façade are wooden, six-over-six double hung sash windows topped with flat, brick arches and set on stone lintels. The wood paneled front door features a carved Federal-style door surround and a four-pane transom. The first story windows are missing their original shutters. The second story windows feature louvered wood shutters attached with decorative iron shutter stops. The slate-covered roof of this portion of the house features four Federal-style dormers (two on either side of the roof) with wooden, double-hung sash windows. The west elevation has two false windows where an interior stair is placed. The rear façade, or north elevation, features a small, gable roof, partially-engaged, one-story porch with a wood pediment over the back door (Photographs 4-8).

The second portion of the house is also two-and-one-half stories and three bays wide, but only one bay deep and somewhat shorter in height than the brick portion of the house. This stone structure is the central portion of the house and possibly pre-dates the brick portion. It has a stone foundation, a slate-covered gable roof, and one exterior-end brick chimney. The stonework on the front façade (south elevation) features quoining and multi-colored stones. The front door is wood paneled and protected by a modern aluminum screen door. The windows on this portion are all wooden, six-over-six, double-hung sash windows. The front façade features a two-story, fully-engaged portico with slender, squared wood columns (Photograph 9-10).

Built in the first half of the twentieth century, the third portion of the house is a one-story frame structure that serves as a kitchen wing. This portion is two bays wide and one bay deep and has a slate gable roof, as well as a two-story, brick exterior-end chimney. The concrete foundation is scored to resemble stone. This portion is sided with weatherboard and also has wooden, six-over-six, double-hung sash windows. The rear façade, or north elevation, has a small wood portico over the wood paneled back door (Photographs 11-13).

As a whole, the three portions of the house represent distinct architectural periods and styles, displaying quality workmanship and a cohesive, balanced design (Photograph 14).

The property contains a Pennsylvania bank barn with a more recent, similar-sized structure attached to its northeast corner. The older section of the barn has a stone foundation, a wood-sided frame structure, and an asphalt-shingled gable roof. The stonework of the stable walls is similar to the stonework on the central portion of the dwelling. It also features an unenclosed forebay that extends over the stable yard. The barn roof has two gabled vents. The south elevation (gable end) has a Victorian-era scalloped, wooden vergeboard at the roofline. The newer portion is also frame and wood-sided with gabled rooftop vents, but has a concrete block foundation. Both sections of the barn are painted red. Near the point where the two segments of the barn are attached sets an orange-colored, tile silo with a conical, asphalt-shingled roof (Photograph 15-19). The property's outbuildings consist of several wood-

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. CE-148

Name Taylor's Venture
Continuation Sheet

Number 7 Page 1

framed or concrete sheds of various sizes and uses. Other structures included a hand-pump and a concrete watering trough (Photographs 20-22).

The landscape surround the farmstead's cluster of buildings still reflects the historic appearance of agricultural farm fields and wooded areas. As there is little modern development in the surrounding area, Taylor's Venture continues to reflect centuries of Cecil County's agricultural heritage (Photographs 23-24).

8. Significance

Inventory No. CE-148

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input checked="" type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other: _____

Specific dates Unknown **Architect/Builder** Unknown

Construction dates c. 1800

Evaluation for:

☒ National Register ☐ Maryland Register ☐ not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

Taylor's Venture is eligible for the National Register of Historic Places under Criterion A for agriculture and Criterion C for architecture. The property has been in agricultural use since the eighteenth century and its buildings are reflective of centuries of Cecil County's rich, rural architectural history.

The seat of the Taylor family for generations, the property known as "Taylor's Venture" dates to the early eighteenth century. A 1720s map notes the area as "Thomas Taylor's Land." The first European ownership of this land was as part of a large patent granted to Irishman George Talbot in 1680 with the provision that he bring six hundred and forty persons of British or Irish descent to settle the area at his own expense. Originally named "Susquehanna Manor," Talbot increased the patent, which was later named "New Connaught Manor," until it extended from the North East River to the Octoraro Creek and from the Chesapeake Bay to a point some miles north of the present boundary between Maryland and Pennsylvania.¹

The name Taylor's Venture most likely originated with John Taylor, who deeded the property to his sons in the late 1790s. During the early 1800s, his son, Captain Thomas Taylor, lived at the property with his wife and ten children, many of whom are buried in a family cemetery on the property. Members of the Taylor family continued to own the land until the mid-nineteenth century.²

Subsequent owners divided the land over the years. Land records indicate that a Samuel Hughes received a deed for a 22 acre tract of land called "The End of All Strife," which included the present estate. By the early twentieth century, the property was once again combined under John E. Jackson's ownership from three separate deeds. In the 1940s, property owners Mr. and Mrs. Alfred C. Bohn, of New York, restored the property to its original colonial appearance. They called the estate "Strife's End," an abbreviation of "The End of All Strife." Since 1962, the Porter family has owned the property reverting to the original name "Taylor's Venture."³

¹ Morton Field Taylor, "A Historical Sketch of Taylor's Venture," *The Upper Shoreman*, Vol. 8 No. 8, 1970, p.3.

² *Ibid.*, p.21.

³ *Ibid.*, p.35.

9. Major Bibliographical References

Inventory No. CE-148

Blumgart, Pamela James et. al. At the Head of the Bay: A Cultural and Architectural History of Cecil County, Maryland.

Crownsville, MD: The Maryland Historical Trust Press, 1996.

Maryland Historical Trust. Historic American Building Survey Inventory. *Strife's End or Taylor's Venture*. 1968.

Taylor, Morton Field. "A Historical Sketch of Taylor's Venture." *The Upper Shoreman* Vol. 8 No. 8 (1970): 1, 3, 15, 21, 29, 35.

10. Geographical Data

Acreage of surveyed property 163 acres

Acreage of historical setting 161 acres

Quadrangle name Harve De Grace

Quadrangle scale: 1:24,000

Verbal boundary description and justification

The boundary for the property is tax parcel 30 68. It is bound roughly by U.S. 40 to the south, Principio Creek to the east, and Winch Road to the west. The boundary encompasses the property's historic structures and includes surrounding agricultural fields, as they are reflective of the property's historic agricultural significance.

11. Form Prepared by

name/title	Melissa Hess/Architectural Historian		
organization	KCI Technologies, Inc.	date	February 2004
street & number	5001 Louise Drive	telephone	717-691-1340
city or town	Mechanicsburg	state	PA

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville, MD 21032-2023
410-514-7600

RESOURCE SKETCH MAP

CE-148

Taylor's Venture
Perryville Vicinity
CECIL COUNTY



WINCH ROAD

CSX RAILROAD TRACKS

POND

EQUIPMENT
SHEDS

OFFICE/SHOP

SHEDS

SILO

BARN

DWELLING

GRAVEL DRIVE

CEDAR TREES

Not drawn to scale

MFH


23 taken from U.S. 40 ↓

Taylor's Venture CE 148

Cecil County, Maryland

1992 USGS Topographic Map
Havre De Grace Quadrangle
1:24,000

0 2000 Feet





CE-148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan. 2004

MD SHPO

Formstead view, Facing NE

1 of 24



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan. 2004

MD SHPO

Landscape View and Drive, Facing E

2 of 24



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan. 2004

MD SHPO

Dwelling, South elevation, Facing N

3 of 24



CE- 148

Taylor's Venture

Cecil County, MD

Melissa Hoss

Jan. 2004

MD SHPO

Dwelling, South elevation, Brick portion, Facing NW

4 of 24



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan. 2004

MD SHPO

Dwelling, front door, facing N

5 of 24



CE-148

Taylor's Venture

Cecil Cnty. MD

Melissa Hess

Jan. 2004

MD SHPO

Dwelling, front door detail, facing N

6 of 24



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan. 2004

MD SHPO

Dwelling, West elevation, Facing SE

7 & 24



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hoss

Jan. 2004

MD SHPO

Dwelling, North elevation, Facing SW

8 & 24



CE-148

Taylor's Venture

Cecil Cnty, MD

Melissa Hess

Jan. 2004

MD SHPO

Dwelling, Sath elev., Stone Portion, Facing N

9 of 24



CE - 148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan. 2004

MD SHPO

Dwelling, South elev, Stone Portion, Facing N

10 & 24



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan: 2004

MD SHPO

Dwelling, South elev., Frame Portion, Facing N

11 of 24



CE- 148

Taylor's Venture

Cecil Cnty, MD

Melissa Hess

Jan. 2004

MD SHPO

Dwelling, East elevation, Facing W

12 & 24



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan. 2004

MD SHPO

Dwelling, North elev, Frame portion, Facing S

13 & 24



CE-148

Taylor's Venture

Cecil Cnty, MD

Melissa Hess

Jan, 2004

MD SHPO

Dwelling, North elevation, Facing SE

14 & 24



CE-148

Taylor's Venture

Cecil Cnty, MD

Melissa Hoss

Jan. 2004

MO SHPO

Barn, South elevation, Facing NW

15 f 24



CE - 148

Taylor's Venture

Cecil County, MD

Melissa Hoss

Jan. 2004

MD SHPO

Born, South elevation, Facing NE

16 & 24



CE-148

Taylor's Venture

Cecil Cnty, MD

Melissa Hoss

Jan. 2004

MD SHPO

Barn, West elevation, Facing E

17 of 24



CE-148

Taylor's Venture

Cecil Carty, MD

Melissa Hess

Jan. 2004

MD SHPO

Barn, Silo, Facing E

18 f 24



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hoss

Jan. 2004

MD SHPO

Barn, North elevation, Facing SE

19 & 24.



CE-148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan 2004

MD SHPO

Outbuildings, Facing NE

20 & 24



CE-148

Taylor's Venture
Cecil Conty, MD

Melissa Hoss

Jan. 2004

MD SHPO

Equipment shed, Facing NW

21 of 24



CE-148

Taylor's Venture
Cecil County, MD

Melissa Hess

Jan. 2004

MD SHPO

Watering Trough,
22 & 24



CE - 148

Taylor's Venture

Cecil County, MD

Melissa Hess

Jan 2004

MD SHPO

Landscape View, Facing N

23 & 24



CE - 148

Taylor's Venture

Cecil Cnty, MD

Melissa Hoss

Jan. 2004

MD SHPO

Form Pond, Facing N

24 of 24

location?

0801485364

Form 10-445
(5/62)

1. STATE <u>Maryland</u> COUNTY <u>Cecil County</u> TOWN <u>Principio Furnace</u> VICINITY <u>Principio Furnace</u> STREET NO. <u>Winch Road, 1.3 mile north of Rt 40</u> ORIGINAL OWNER ORIGINAL USE <u>dwelling</u> PRESENT OWNER <u>George F. Porter</u> PRESENT USE <u>dwelling</u> WALL CONSTRUCTION <u>Brick - stone - frame</u> NO. OF STORIES <u>2 1/2 - 2 - 1</u>		HISTORIC AMERICAN BUILDINGS SURVEY CE-148 INVENTORY CE-148	
2. NAME <u>Strife's End or Taylor's Venture</u> DATE OR PERIOD <u>early 19th Century</u> STYLE <u>Federal</u> ARCHITECT BUILDER		3. FOR LIBRARY OF CONGRESS USE	
4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION OPEN TO PUBLIC <u>No</u>			
<p> <i>(three-part)</i> Strife's End (or Taylor's Venture) is a telescopic house of three parts. The largest portion is a two-and-one-half-story brick structure, resembling a federal townhouse, three bays long and two bays deep. The brick is laid in common bond, and there are flat arches over the windows of the south facade. There are two dormers on the roof. The northwest bays on the gable are false windows, undoubtedly where the stair is placed (as at Holly Hall and Mt. Ararat). </p> <p> The second portion of the house is a three-bay one-room deep granite structure which may pre-date the brick portion. The south facade has a center door, but the north door is located on the westernmost bay. There is a two-story porch in front of the stone section. </p> <p> To the east of the stone house is a two-bay one-story frame wing which appears to be a recent addition. </p> <p> <i>The windows on the NW gable are false Clarif's false are there at Mt. A. wind at 1/2 or just staircase behind wall too?</i> </p>			
5. PHYSICAL CONDITION OF STRUCTURE Endangered <u>No</u> Interior <u>g</u> Exterior <u>good</u>			
6. LOCATION MAP (Plan Optional)		7. PHOTOGRAPH <u>CE. 3178</u>	
8. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC. <u>The Upper Shoreman, Aug, 1963</u>		9. NAME, ADDRESS AND TITLE OF RECORDER <u>Michael Bourne</u> <u>Maryland Historical Trust</u> DATE OF RECORD <u>April 17, 1968</u>	

SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE



Strife's End

CE - 148

Taylor's Venture

South Elevation

MOB/1968

NEG - MD Hist. Trust